

GOK Zagreb



Opis radova na gradilištu

Zaštita iskopa na Glavnom odvodnom kolektoru u Zagrebu na lokaciji Radnička cesta-Slavonska Avenija. Iskopna jama zaštićena je čeličnim talpama ARBED AU 16. Dubina zabijanja talpi iznosi 6,00-12,00 m a zahvaljujući dobrim geološkim uvjetima osiguran je rad u suhom. Radi postizanja zahtijevane dinamike na gradilištu, radovi su vršeni i noću. Na lokacijama gdje nije bilo moguće izvesti zaštitu čeličnim talpama, ista je ostvarena tehnologijom berlinskog zida.

Mjere

čelične talpe AU 16:	9 326 m ²
razupore:	20 t
bušeni piloti Ø 560 mm:	50 m

Naručitelj

Hidroelektra niskogradnja d.d.

Investitor

Grad Zagreb

Vrijednost radova

6 321 780,30 kn

Godina

2004



GOK Zagreb



Contract description

Pit protection at GOK (main sewage collector) in Zagreb located on Radnička-Slavonska street junction. Works were carried out by means of ramming steel sheet piles ARBED AU 16. The length of the sheet piles was 6,00-12,00 m and due to favorable geological conditions dry working conditions were secured. In order to meet required terms on the site works were carried out by night. On specific locations where it was not possible to install the sheet piles the pit protection was carried out by rider bracing wall.

Measures

piles steel sheet piles AU 16:	9 326 m ²
spreaders:	20 t
piles dia. 560 mm:	50 m

Client

Hidroelektra niskogradnja d.d.

Investor

City of Zagreb

Price

6 321 780,30 kn

Year

2004



ZAKLADANI STAVEB®

ZAKLADANI STAVEB d.o.o.
10000 ZAGREB, PANTOVČAK 24

TEL.: +385 1 6197 324 / 325
FAX.: +385 1 6196 245

www.zakladani.cz
E-mail: zakladni@zg.htnet.hr