

Čabar– Zamost



Opis radova na gradilištu

Zaštita iskopa građevinskih jama u koritu rijeke Kupe na dionici lokalne ceste Zamost–Hrvatsko kraj Čabra. Zaštita se je izvodila čeličnim žmurjem tipa L III n, dubine zabijanja 5,0 m, a sve u svrhu izrade stupišta i upornjaka budućeg mosta. Radovi su izvedeni u otežanim geološkim i hidrološkim uvjetima, u aluvijalnim kamenim nanosima i formacijama šejla.

Mjere

Žmurje LIII n: 295 m²

Naručitelj

Hidroelektra Niskogradnja

Investitor

Primorsko–Goranska Županija

Vrijednost radova

160 000 kn

Godina

2003

Kolodvor Sisak



Opis radova na gradilištu

Zabijanje čeličnog žmurja tipa AU 16 u svrhu zaštite iskopa servisne građevinske jame objekta GLAVNI KOLEKTOR u Sisku. Dubina zabijanja čeličnog žmurja bila je 8,0 m. Radovi su se izvodili u glinovitim i šljunkovitim materijalima.

Mjere

Žmurje AU16: 220 m²

Naručitelj

Hidroelektra Niskogradnja

Investitor

Grad Sisak

Vrijednost radova

233 500 kn

Godina

2003

Bunari



Opis radova na gradilištu

Izrada bunara za za odvodnjavanje trase autoceste Zagreb–Rijeka.

Mjere

Bunari Ø 90 cm: 108 m

Naručitelj

Strabag

Investitor

AC Rijeka–Zagreb

Vrijednost radova

305 000 kn

Godina

2002

Čabar – Zamost Bridge



Contract description

Protection of a foundation pit of the bridge over the Kupa River on the part of a local road Zamost–Hrvatsko near Čabar. The pit was protected with steel sheet piles L III n, ramming depth reached 5 m both for the piles and abutment foundations of the future bridge. Works were executed under very heavy geological, hydrological and meteorological conditions in rocky alluvial layers.

Measures

sheet piles LIII n 295 m²

Client

Hidroelektra Niskogradnja

Investor

Primorsko–Goranska Županija

Price

160 000 kn

Year

2003

Kolodvor Sisak



Contract description

Opening shaft for micro-tunneling of a Sisak town main collector. The shaft was protected by steel sheet piles AU 16 of 8 m length. Soil conditions were clay and gravel.

Measures

sheet piles AU16 220 m²

Client

Hidroelektra Niskogradnja

Investor

Grad Sisak

Price

233 500 kn

Year

2003

Dewatering wells



Contract description

Execution of dewatering wells on the Zagreb–Rijeka motorway.

Measures

Dewatering wells dia 90 cm: 108 m

Client

Strabag

Investor

AC Rijeka–Zagreb

Price

305 000 kn

Year

2002

